



Loop 360 Program Update

Lucas Short, P.E. Loop 360 Program Manager



Agenda

- Loop 360 Program Overview
- Westlake Drive/Cedar Street Construction Overview
- Courtyard Drive/RM 2222
 - Need for Improvements
 - Project Process and Timeline
 - Project Overview (and look at specific elements)
 - Anticipated Construction Phasing
 - January HOA discussion items follow-up
- Additional Loop 360 Projects
- Stay Informed
- Q&A



About the Loop 360 Program


Program purpose: Upgrade multiple intersections to improve mobility and safety along the corridor.

- Eliminate at-grade crossings.
- Install over/underpasses at major intersections.
- Separate local and through traffic at intersections.
- Add a diverging diamond interchange (DDI) at RM 2222; evaluate a DDI at RM 2244.
- Increase safe access to/from adjoining neighborhoods.

Loop 360 Program

Projects:


- Westlake Drive/
 Cedar Street.
- Courtyard Drive/ RM 2222.
- Lakewood Drive/Spicewood Springs Road.
- RM 2244.
- MoPac to RM 2244.



Westlake Drive/Cedar Street

- Remove traffic signal from Loop 360 mainlanes at Westlake Drive and Cedar Street.
- Construct an underpass at both intersections, including non-signalized U-turns in both directions at Westlake Drive.
- Environmentally cleared spring 2020.
- Construction began in June 2022.
- Construction is expected to take approx. 3 years.
- Currently crews are working on utility relocations, retaining walls and drainage lines.






Westlake Drive Cliff Cuts




Courtyard Drive/RM 2222 (Need for Improvements)

- Why this project is needed:
 - 36 crashes on this area Loop 360 between 2019 and 2023.
 - 2 included fatalities
 - 14 were at the Courtyard/Loop 360 Intersection
 - Over the last 5 years sections of Loop 360 have been ranked in the top 100 most congested roadways in Texas.
 - It takes approximately 78-84% longer to travel on Loop 360 during peak periods than during free-flow conditions.
 - If nothing is done by 2040:
 - Morning peak travel times could further increase by an average of 46%.
 - Evening peak travel times could be nearly double the off peak/free-flow travel times.



Project process and timeline





Construction Phase:


- Currently authorized for construction funding in 2026.
- Actual construction start is TBD.
- Estimated total construction duration is approximately 3 years.

*Graphic represents current status of Courtyard Drive/RM 2222 project.

Courtyard Drive/RM 2222 (Project Overview)


Project overview:

- Remove traffic signal from Loop 360 mainlanes at Courtyard Drive and construct an underpass.
- Reconfigure RM 2222 at Loop 360 to a diverging diamond interchange (DDI).
- Add a shared-use path and sidewalks within the project limits.
- Access changes from eastbound Courtyard Drive to southbound Loop 360 and from northbound Loop 360 to eastbound Courtyard Drive.
- Northbound exit ramp replaced with northbound braided ramps.
- Southbound entrance ramp replaced with southbound braided ramps




Courtyard Drive/RM 2222 Cross Section






Loop 360 looking south at Courtyard Drive





Loop 360 looking north toward RM 2222





Courtyard Drive looking east





Courtyard Drive/RM 2222 Cross Section





January Courtyard HOA Meeting Follow-up

Tennis Club Sign located in TxDOT ROW

- HOA to decide: relocate existing sign or have new one made?
- TxDOT will provide location options based on sign size.

Irrigation located in TxDOT ROW

- HOA responsible for cutting & capping irrigation prior to construction.
- TxDOT will provide HOA notice several months before construction begins.

Landscaping stones located in TxDOT ROW

- TxDOT will identify which stones must remain for retaining wall.
- HOA to identify stones to be salvaged. Remaining stones will become contractor's property.
- HOA will have opportunity to reclaim/move stones that are not structurally necessary several months prior to construction letting.

Fencing along cliff


- TxDOT provides two options chain link or barbed wire.
- HOA can install its own fence/barrier along the neighborhood property line.
- TxDOT can work with HOA on timing of fence installation.





Diverging Diamond Interchange at RM 2222 Intersection





Courtyard Drive/RM 2222 – Anticipated Construction Phasing


- Phase 1:
 - a) Rock excavation
 - b) Construction of all elements outside of Loop 360 main lanes
- Phase 2: Courtyard Bridge Construction
 - Eastside access at southern Courtyard
 Drive intersection will be closed (est.
 6-7 months)
- Phase 3: RM 2222 DDI Construction

360 Fo Guang Shan Xiang Yun Temple **Bull Creek** NORTH CAT **Project Limits** MOUNTAIN BRIDGEHEAD Austin Fire Station #31 THE COURTYARD 2222 **Bull Creek Project Limits** CAT MOUNTAIN. (360)Austin Country Club

Phasing and timeframes subject to change

Courtyard Drive/RM 2222 Cross Section





Additional Loop 360 projects

- Lakewood Drive / Spicewood Springs Road
 - Construct overpasses at Spicewood Springs Road (E)/Bluffstone Drive and Lakewood Drive with non-signalized Uturns in both directions.
- MoPac to RM 2244
 - Construct an overpass at Walsh Tarlton Lane and either an overpass or an underpass at Lost Creek Boulevard and Westbank Drive.
 - Construct continuous one-way northbound and southbound frontage roads throughout the project limits to improve local connectivity.
- RM 2244 evaluate a DDI
- Projects will move forward as additional funding becomes available.





How can I stay informed?

Visit the program website: https://www.txdot.gov/loop360

Questions or Comments? Email the project team: KSETH-C@txdot.gov